

SPEC NOTE: This Section specifies PostDrive SpeedGate, an electronic high speed, vehicular perimeter security gate, suitable for airports, port authorities, military bases, money-transport companies and other locations requiring strict safety measures.

PART 1 GENERAL

- 1.1 THE TOP TRACK SPEEDGATE IS A POST DRIVEN ELECTRICALLY OPERATED FAST ACTING BI-FOLD GATE.**
- 1.2 ALL STRUCTURAL COLUMNS, DRIVE UNIT, CONTROLLER, GATE PANELS BY WALLACE INTERNATIONAL**
- 1.3 RELATED SECTIONS**
 - .1 Section [01330] [01 33 13] Submittal Procedures].
 - .2 Section [01355] [01 74 20] – Construction Waste Management and Disposal.
 - .3 Section [01780] [01 78 00] Closeout Submittals].
 - .4 Section [_____] - [_____]: Fencing
 - .5 Section [03300] [03 30 00] - Cast-in-Place Concrete: Structural portal foundations.

SPEC NOTE: Coordinate the following paragraph with electrical sections to ensure electrical supply is provided to suit the gate requirements. Normally the electrical power supply to terminal box in each unit is specified in Division 16. All remaining electrical work is specified in this Section.

- .6 Section [___] – [_____]: Electrical service and connections.

1.4 SUBMITTALS

- .1 Shop Drawings:
 - .1 Submit final assembly drawings in accordance with Section [01330 Submittal Procedures].
 - .2 Indicate electric power requirements, installation details, wiring diagrams.
- .2 Installation instructions:
 - .1 Submit two copies of manufacturer's written installation instructions.
 - .2 Submit reference list of five (5) installations of the specified type within the last 2 years.
- .3 Test reports:
 - .1 Drive unit shall bear a label indicating that the gate controller/operator mechanism has been tested certified to UL 325 and CSA C22.2 No. 247 standards for all electrical components.

1.5 CLOSEOUT SUBMITTALS

- .1 Provide operation and maintenance data for gate for incorporation into manual specified in Section [01780 Closeout Submittals].
- .2 Conduct comprehensive demonstration for maintenance staff on operation and care of gate.

1.6 QUALITY ASSURANCE

- .1 Manufacturer: A company specializing in the manufacture of electric gate operators.
- .2 Installer: A minimum of three years experience installing similar equipment and approved by manufacturer.

PART 2 PRODUCTS

2.1 HIGH SPEED VEHICLE ACCESS GATE

- .1 Manufacturers:
 - .1 Wallace International,
Model: PDDT *SpeedGate*
Contact: Wallace International:
90 Lawson Crescent, Winnipeg, Manitoba Canada, R3P 2H8
T. 866.300.1110 F. 204.284.1868
www.wallaceintl.com

2.2 MATERIALS

- .1 Steel sheet: hot dipped galvanized to ASTM A653/A653M, A36 pre galvanized steel
- .2 Steel sections: to ASTM (Canadian Equivalent - CAN/CSA G40.21) Grade [300W] [350W].
- .3 Welding materials: to ASWD 1.1 (Canadian Equivalent - CSA W59.)
- .4 Electrical components: Complete gate system to be UL325 listed and/or CSA C22.2 No.247 and complying with local requirements.
- .5 Power Supply: 208/240 V – 20 Amp single phase power supply.

2.3 COMPONENTS

- .1 Gate Columns:
 - .1 Formed steel columns, anchored to concrete foundation.
 - .2 Columns to be 12" square with a wall thickness of .250".
- .2 Model PDDT:
 - .1 Dimensions: [max 20] ft high x [max 24] ft clear opening
 - .2 Panels to be capable of fully opening within 7 seconds
 - .3 Panels: [1.5" vertical bar infill] [non-climbable infill][6 gauge welded wire infill][6 gauge woven wire infill]
 - .4 Manufacturer's standard corrosion resistant hinges. Hinges are to be heavy duty corrosion resistant base material with a minimum 1 3/16" stainless steel shaft.
 - .5 Fully compliant with ASTM F2200 – 05, Class I through Class IV

Spec Note: Safety devices are installed to minimize likelihood of vehicle or pedestrian injury/entrapment. Edit the following paragraphs for safety feature options required for project.

Manufacturer's Note: Complete gate system to be UL325 listed and/or CSA C22.2 No.247 and complying with local requirements

- .3 Safety/Obstruction Devices:
 - .1 Provide reduced speed sensor - Absolute encoder mounted directly to drive motor rotor to act as primary entrapment detection device
 - .2 Photoelectric transmitter and receiver: Equip each column with [2] built-in photocells at 20" [and] [60] inches above the base plate. To be mounted within the columns.
 - .3 Provide 2 channel obstruction loop relay card for integration of dual obstruction loops

Manufactures Note: Control unit to be located within 30 ft. of the gate structure, 2 conduits (recommend 2") for communication/power cabling to gate structure. Control unit not to be mounted within arm's reach of the automated gate.

- .4 Drive Unit:
 - .1 Provide variable frequency drive with programmable logic controller for controlling electro-mechanical drive system. Drive system to incorporate encoders with reduced speed sensing software as primary entrapment detection device.
 - .2 All drive electrical components to be enclosed in weather-resistant housing.
 - .3 Dual .75 HP 3 Phase gear motors with integrated brake and 360:1 gear reduction box with synthetic lubricant
 - .4 Emergency override: Provide secured access panel for manual opening and closing in case of power failure/malfunction.
 - .5 Electrical motors, control units, relays and other electrical components: to ___ approval.

2.4 FINISHES

- .1 Select from:
 - .1 [Hot dip galvanized finish [0.5] kg/m² zinc coating to ASTM A653/A653M (CAN/CSA G164)]
 - .2 [Powder coated to 80 micron thickness - standard RAL colors- check with manufacturer before specifying color]

2.5 PRODUCT OPTIONS

- .1 [Anti climb perforated steel]
- .2 [Anti climb infill to run between panels vertically in line with hinges]
- .3 [Red / Green traffic lights]
- .4 [Second through beam safety photo eye mounted 48" above base plate or in static bollard]
- .5 [Fence Mounting Devices: Provide mounting brackets for mounting chain link fabric to vertical columns]
- .6 [UPS Backup: Provide Uninterruptible Power Supply to variable speed gate controller for emergency operation in event of power outages]

PART 3 EXECUTION

3.1 INSTALLATION

- .1 Provision of concrete foundations as determined by local engineer according to drawings provided.
- .2 .2Install high-speed security gate to manufacturer's written instructions.

3.2 CLEANING AND MAINTENANCE

- .1 Perform cleaning and maintenance procedures in strict accordance with manufacturer's written instructions.
- .2 Maintain logbook of repairs and maintenance.

END OF SECTION